



FIT OUT OF THE LOCKER ROOMS (WARDROBE) FOR THE GYM AT THE PRIMARY SCHOOL 'VASIL GLAVINOV'- SKOPJE

Facility: Primary School 'Vasil Glavinov'

Location of the Facility: Skopje

Country: Republic of Macedonia

BILL OF QUANTITIES FOR REHABILITATION WORKS					
A. General Items					
No.	Description	Unit	Qty.	Unit price	Total price
Contractual Items					
1	Preparation of the Technical Specification, Drawings and follow-up of the Works by an Engineer	L.S	1.00	600.00	600.00
2	Allow for Contractor Mobilization and Demobilization for all facilities as such is field office, site yard, equipment, labour safety and protective clothing, ext. in order to execute the works	L.S	1.00	100.00	100.00
Total for General Items					700.00
B. Bill of Quantity for Reconstruction works					
DEMOLITION AND PREPARATION WORKS					
No	Description	Unit	Qty.	Unit price	Total price
3	Removal of the existing furniture, floor and debris to a disposal	m2	36.00	5.00	180.00
4	Removal of existing internal doors, including the frame	pcs.	2.00	20.00	40.00
Total					220.00
INTERNAL FINISHING WORKS					
No	Description	Unit	Qty.	Unit price	Total price
5	Mending and Plastering and Painting of the walls including damaged parts during the disassembling of the existing doors and other works with cement mortar in 2 layers (rough and smooth) as necessary	m2	105.00	3.50	367.50
6	Plastering and Painting of the ceiling with one fine layer of gypsum lime up to a smooth surface.	m2	35.00	3.50	122.50
Total					490.00
JOINERY AND LOCKSMITH WORK					
No	Description	Unit	Qty.	Unit price	Total price
7	Supply, transport and fixing of Wooden Internal door of min 4cm thick, surfaces white or equivalent after the approval by the Client. Including the frame and lock and other fittings Dim. 90/210 ALL MEASUREMENTS TO BE TAKEN ON THE SITE BY THE CONTRACTOR	pcs.	2.00	300.00	600.00
8	Repairmen of the wooden existing windows to open and close properly, replacemnt of the existing broken glass, and painting of the wooden frame with oil based paint	m2.	8.00	20.00	160.00
Total					760.00

Floor and Ceramic Works					
No	Description	Unit	Qty.	Unit price	Total price
9	Supply, transport and making of the floors with ceramic tiles min 10mm placed above the existing concrete slab, including skirting along the perimeter of the walls. The pattern and the colour of the tiles will be determined by the Client	m2	35.00	20.00	700.00
10	Supply, transport and placing ceramic tiles at the wall to some of the wall, min 10mm thick up to a height 120cm. The pattern and the colour of the tiles will be determined by the Client	m2	18.00	20.00	360.00
Total					1,060.00

Carpenter Works					
No	Description	Unit	Qty.	Unit price	Total price
11	Supply, transport and assembling of lockers made from veneered plywood in modules dim 100/160/45 with 3 lockers with all fittings doors, locks, cylinders and keys, for placing the clothes and bags for the children, colour and design determined by the Client	pcs	10.00	85.00	850.00
Total					850.00

8. Kitchen					
No	Description	Unit	Qty.	Unit price	Total price
8.1	Supply, transport and assembling of the new lights, with neon tubes including all the fittings, necessary intervention in the electrical installation (dim 60x60)t.	pcs	4.00	60.00	240.00
Total					240.00

Bill of Quantities GRAND SUMMARY	
Total Value exclusive of 18% VAT EURO	4,320.00
VAT 18 % EURO	777.60
Total Value inclusive of 18% VAT EURO	5,097.60